



**27th Street Water Service Project
Addendum #1**

Date of Issue: November 4th, 2014
Date of Opening: Unchanged – 1:00 p.m. on November 7, 2014

Notice to All Plan holders:

This Addendum #1, containing the following revisions, additions, deletions and/or clarifications is hereby made part of the Plan and Contract Documents for the above-named project. Bidders shall take this Addendum into consideration when preparing and submitting their bids and it shall be attached to the Contract Documents.

Contractors shall acknowledge receipt of this Addendum #1 in the place provided Proposal Form (page LD-6). Failure to do so may disqualify the Bidder from consideration of its bid.

CONTRACT DOCUMENTS

1. Plan sheet 4 of 4, Detail 1 Asphalt Trench Restoration Detail & Special Provisions Section 7-15.2; Clarification:
 - a. The reference to within 2 feet of concrete or paved surface is intended to mean as measured horizontally. All trench backfill under paved surfaces and within 2-feet (as measured horizontally) shall be CSTC. Trench backfill 2-feet (as measured horizontally) or more from the edge of pavement may be select native trench backfill.
2. Water main material clarification:
 - a. Existing water main located along project is 8" PVC.
3. Plan sheet 4 of 4, Detail W1 5/8" or 3/4" Water Service Connection Detail Note 5; Clarification:
 - a. Upon approval from the engineer the depth of cover for water service lines may be reduced to a depth of 18" minimum below finished grade when required to obtain vertical separation between the existing sewer main and water service lines.

ALL OTHER REQUIREMENTS OF THE CONTRACT DOCUMENTS REMAIN IN EFFECT.

Please call or email if you have any further questions to (253) 922-9315 or Kgil@cityoffife.org.

Sincerely,

Terry Wright, P.E.

Attachment: NONE

