

SCHEDULE OF PRICES

ITEM	SECTION	UNIT	EST QTY	DESCRIPTION	CONTRACTOR BID	
					UNIT PRICE	COST
1	1-09	LS		Mobilization		
2	2-01	LS	1	Clearing and Grubbing		
3	2-02	SY	550	Removing Asphalt Conc. Pavement		
4	2-02	LS	1	Removal of Structure and Obstruction		
5	2-02	SY	154	Removing Cement Conc. Sidewalk		
6	2-02	LF	231	Removing Cement Conc. Curb and Gutter		
7	2-02	LF	80	Removing Guardrail		
8	2-02	LS	1	Removing Miscellaneous Traffic Item		
9	2-02	LS	1	Removal and Disposal of Asbestos Material		
10	2-02	FT-IN	2624	Sawcutting Asphalt/Cement Conc. Pavement		
11	2-03	CY	140	Ditch Excavation		
12	7-04	LF	42	Corrugated Polyethylene Storm Sewer Pipe 18 IN Diam		
13	7-04	LF	75	Corrugated Polyethylene Storm Sewer Pipe 24 IN Diam		
14	7-05	EA	4	Connection to Drainage Structure		
15	7-04	LF	117	Testing Storm Sewer Pipe		
16	7-17	LF	90	High-Density Polyethylene (HDPE) Pipe 4 In. Diam		
17	7-17	LF	90	Testing Sewer Pipe		
18	7-17	LF	164	Ductile Iron Pipe For Water Main 12 In Diam.		
19	7-12	EA	7	Gate Valve 12 IN		
20	9-03	CY	214	Permeable Ballast		

ITEM	SECTION	UNIT	EST QTY	DESCRIPTION	CONTRACTOR BID	
21	9-30	EA	1	Comb. Air Release/Air Vacuum Valve Assembly 2 IN.		
22	2-09	CY	1100	Structure Excavation Cl A		
23	6-01	LF	60	Bridge Railing Type Chain Link Fence		
24	7-02	LS	1	Precast Reinf. Conc. Box Culvert No.		
25	2-09	LS	1	Shoring or Extra Excavation Class A		
26	9-03	TON	520	Gravel Base		
27	4-04	TON	3302	Crushed Surfacing Base Course		
28	4-04	TON	96	Crushed Surfacing Top Course		
29	9-13	TON	560	Quarry Spalls		
30	5-04	TON	205	HMA CL. 1/2 In. PG 64-22		
31	5-04	SY	100	Plaining Bituminous Pavement		
32	8-01	EA	6	Inlet Protection		
33	8-02	EST	1	Erosion/Water Pollution Control		
34	8-01	AC	0.12	Seeding, fertilizing, and Mulching		
35	8-01	LF	740	High Visibility Fence		
36	8-04	LF	110	Extruded Curb		
37	8-11	EA	9	Box Culvert Guardrail Steel Post Type 2		
38	8-11	LF	67	Beam Guardrail Type 31		
39	8-22	SF	448	Painted Crosswalk Line		
40	8-22	LF	58	Painted Stop Line		
41	8-22	LF	8	Painted Wide Line		
42	8-21	LF	45	Painted Line		
43	8-20	LS	1	Traffic Signal System Complete (54th Ave E & 8th St E)		
44	1-10	LS	1	Project Temporary Traffic Control		

ITEM	SECTION	UNIT	EST QTY	DESCRIPTION	CONTRACTOR BID	
45	1-10	HR	3840	Portable Changeable Message Sign		
46	8-04	LF	164	Cement Conc Traffic Curb and Gutter		
47		LS	1	Temporary Stream Diversion		
48	7-05	EA	2	Remove and Reset Catch Basin		
49	2-09	CY	538	Structure Excavation Class B Incl. Haul		
50	2-09	SF	512	Shoring or Extra Excavation Trench		
51	9-03	CY	142	Gravel Backfill for Pipe Zone Bedding		
52	1-54	LS	1	Roadway Surveying		
53	8-14	SY	50	Cement Conc. Sidewalk		
54	8-06	SY	68	Cement Conc. Driveway Entrance Type 1		
55	2-11	LS	1	Trimming and Cleanup		
56		LS	1	Record Drawings		
57	1-04	EST	1	Minor Change	EST	\$10,000.00
58	7-17	LF	122	Ductile Iron Pipe For Water Main 12 In Diam.		
59	7-12	EA	2	Gate Valve 10 IN		
60	7-17	LF	15	Ductile Iron Pipe For Water Main 6 In Diam.		
61	7-09	LF	20	HDPE Pipe for Water Main 16 In Diam.		
62		LF	6	Steel Casing for Water Main 28 In Diam		
63	9-33	SY	1037	Construction Geotextile for Separation		
64	7-08	LS	1	Dewatering		
65		CY	10	Pavement Repair Excavation Incl Haul		
66	7-14	EA	1	Hydrant Assembly		
					SUBTOTAL	

Sales Tax Rule 170 - WSDOT R/W

67	7-09	LF	220	HDPE Pipe for Water Main 16 In Diam.		
68		LF	220	Steel Casing for Water Main 28 In Diam		
					Sales Tax	
					9.9%	
					SUBTOTAL	

TOTAL _____