

**Department of Public Works  
Fife, Washington 98424**

**July 3, 2014**

**ATTENTION: All Bidders and Planholders**

**BROOKVILLE AND OXBOW WETLAND MITIGATION  
FMSIB-0450(002) Addendum No. 1**

The Amendments, Special Provisions, Plans, and Proposal for this project are amended as follows:

**Special Provisions**

Add the following new Section:

**1-02.0 Pre-Bid Meeting**

The Contracting Agency will hold one voluntary pre-bid meeting on Tuesday, July 8, 2014 for Bidders.

The meeting will take place from 9:00 a.m. to 11:00 a.m. It will begin in the parking lot south of Valley Avenue East, 6506 Valley Avenue East, Fife, WA 98424. This part of the meeting will consist of a tour through the two sites followed by questions and discussion of general requirements.

The City and their consultants will be explaining key issues on the project and will be available to answer questions. If bidders have specific questions, please provide them via email before the meeting to [kgill@cityoffife.org](mailto:kgill@cityoffife.org).

Questions will be addressed as described in Section 1-02.4. Minutes to the meeting will be distributed to all plan holders via Addendum.

All Bidders are encouraged to attend.

The supplement to:

**1-07.5(2) State Departments of Fish and Wildlife**

On pages S-21 through S-22 and S-38 through S-39 is hereby deleted in its entirety.

**1-07.18(2) Additional Insured**

Add the following to the list of additional insured in Section 1-07.18(2):

- BergerABAM, Inc.
- Widener and Associates

### **Plans**

No changes to the plan sheets have been made as part of this Addendum.

### **Proposal**

On the revised bid schedule per the attached, Bid Item No. 53 is NEW.

### **Questions from Prospective Bidders:**

1. When would you anticipate a planting date for this project...this fall or spring/fall 2015?  
**Answer: The Contract provides for 80 working days, which includes time to plant everything this fall. However, it is possible that due to schedule delays final planting may need to occur in 2015. If so, Section 1-08.6 of the WSDOT Standard Specifications would apply.**
2. In the plant material column it calls for 1 gallon container/live stake. Would it be possible to clarify what exactly that means? Same scenario for the bare root/plug  
**Answer: The Contractor has the option of providing the plant material in a 1 gallon container (with soil) or as a live stake (cuttings) when noted as such. Similarly, they have the option of providing the emergent plant materials with bare roots or as a plug (a small amount of soil attached).**

Bidders shall furnish the City with evidence of the receipt of this addendum. This addendum will be incorporated in the contract when awarded and when formally executed.

**City of Fife**  
**Wapato Creek Wetland and Stream Mitigation Phase I**

NOTE: Unit prices for all items, all extensions and total amount must be shown in ink or typewritten. Show unit prices in figures only.

ITEM NO.	BASE BID ITEM	QUANTITY	UNIT	UNIT PRICE	TOTAL PRICE
<b>Section 1: Preparation</b>					
1	Mobilization	1	LS	\$	\$
2	Clearing and Grubbing	10.00	AC	\$	\$
3	Roadway Surveying	1	LS	\$	\$
4	Minor Change	1	CALC	Force Account	\$25,000.00
<b>Section 2: Grading</b>					
5	Site Excavation and Haul	15,178	CY	\$	\$
6	Unsuitable Foundation Excavation Incl. Haul	67,356	CY	\$	\$
7	Embankment Compaction	15,178	CY	\$	\$
8	Wetland Excavation Zone E Including Haul	8,981	CY	\$	\$
<b>Section 4: Surfacing</b>					
9	Streambed Gravel	540	TON	\$	\$
<b>Section 17: Erosion Control and Planting</b>					
10	Silt Fence	2,374	LF	\$	\$
11	High Visibility Fence	3,370	LF	\$	\$
12	ESC Lead	40	DAY	\$	\$
13	Temporary Seeding	2.2	ACRE	\$	\$
14	Wetland Seed Mix	13	ACRE	\$	\$
15	Compost Blanket 4 Inches Thick	13	ACRE	\$	\$
16	Topsoil Type B	3,327	CY	\$	\$
17	Rototilling – 8 Inch Depth	60,840	SY	\$	\$
18	Stabilized Construction Entrance	540	SY	\$	\$
19	Street Cleaning	500	HOUR	\$	\$
20	Wattle	1,882	LF	\$	\$
21	Inlet Protection	2	EA	\$	\$
22	Erosion/Water Pollution Control	1	FA	Force Account	\$80,000.00
23	PSIPE – Acer Macrophyllum/Big Leaf Maple, 1 Gal. Cont.	604	EA	\$	\$

24	PSIPE – Pseudotsuga Menziesii/Douglas Fir, 1 Gal. Cont.	403	EA	\$	\$
25	PSIPE – Thuja Plicata/Western Red Cedar, 1 Gal. Cont.	1,745	EA	\$	\$
26	PSIPE – Prunus Emarginata/Bitter Cherry, 1 Gal. Cont.	403	EA	\$	\$
27	PSIPE – Acer Circinatum/Vine Maple, 1 Gal. Cont.	4,835	EA	\$	\$
28	PSIPE – Gaultheria Shannon/Salal, 1 Gal. Cont.	2,417	EA	\$	\$
29	PSIPE – Oemieria Cerasiformis/Indian Plum, 1 Gal. Cont.	2,417	EA	\$	\$
30	PSIPE – Sambucus Racemosa/Red Elderberry, 1 Gal. Cont.	3,223	EA	\$	\$
31	PSIPE – Symphoricarpos Albus/Common Snowberry, 1 Gal. Cont.	3,223	EA	\$	\$
32	PSIPE – Salix Lucida/Pacific Willow, 1 Gal. Cont./Live Stake	1,521	EA	\$	\$
33	PSIPE – Populus Balsamifera/Black Cottonwood, 1 Gal. Cont.	854	EA	\$	\$
34	PSIPE – Malus Fusca/Western Crabapple, 1 Gal. Cont.	4,555	EA	\$	\$
35	PSIPE – Lonicera Involucrata/Black Twinberry, 1 Gal. Cont.	9,083	EA	\$	\$
36	PSIPE – Cornus Sericea/Red Twig Dogwood, 1 Gal. Cont.	7,563	EA	\$	\$
37	PSIPE – Ribes Lacusre/Black Gooseberry, 1 Gal. Cont.	5,694	EA	\$	\$
38	PSIPE – Carex Obnubta/Slough Sedge, Bare Root/Plug	30,839	EA	\$	\$
39	PSIPE – Scirpus Microcarpus/Small Fruited Bulrush, Bare Root/Plug	20,559	EA	\$	\$
40	PSIPE – Eleocharis Palustris/Common Spikerush, Bare Root/Plug	20,559	EA	\$	\$
41	PSIPE – Juncus Ensifolius/Daggerleaf Rush, Bare Root/Plug	30,839	EA	\$	\$
42	PSIPE – Fraxinus Latifolia/Pacific Willow, 1 Gal. Cont./Live Stake	286	EA	\$	\$
43	PSIPE – Physocarpus Capitatus/Pacific Ninebark, 1 Gal. Cont.	1,487	EA	\$	\$
44	PSIPE – Salix Sitchensis/Sitka Willow, 1 Gal. Cont./Live Stake	1,869	EA	\$	\$
45	Plant Establishment – Second Year	1	FA	Force Account	\$10,000.00
46	Bark or Wood Chip Mulch	530	CY	\$	\$
47	Tree Protection Device	52,182	EA	\$	\$
48	Irrigation System	1	LS	\$	\$
49	Large Woody Debris	66	EA	\$	\$
50	SPCC Plan	1	LS	\$	\$

**Section 19: Other Items**

51	Roadside Cleanup	1	FA	Force Account	\$5,000.00
52	Decommission Monitoring Well	1	EA	\$	\$
53	Project Temporary Traffic Control	1	LS	\$	\$
<b>Base Bid Total</b>					<b>\$</b>